

Phase 1 Sanitary Sewer System Rehabilitation
Addendum No.1

**Town of Ayer, MA
Department of Public Works**

October 16, 2019

**Addendum No. 1
to
Contract Documents
For
Phase 1 Sanitary Sewer System Rehabilitation
October 2019**

<p>BIDDERS MUST ACKNOWLEDGE RECEIPT OF THIS ADDENDUM No.1 IN THEIR ITEMIZED PROPOSAL</p>

Bidders are hereby informed that plans and specifications for the above-mentioned project are modified, corrected and/or supplemented as follows, and that Addendum No. 1 becomes part of the Contract Documents.

Contract Specifications

Item 1-1: Section 33 01.30.72 – Cured-in-Place Pipe Lining

Paragraph 3.5

DELETE in its entirety and REPLACE with the following

“3.5 POST-CONSTRUCTION INSPECTION OF COMPLETED WORK

- A. Provide Post-construction Inspection video documentation showing completed work in accordance with Section 33 01 30.16, Television inspection of Sewers. Perform Post-Construction Inspection immediately following completion of lining work and no later than 60 days after the completion of the lining work. In segments with lateral lining work, perform Post-Construction Inspection after all lateral lining work is complete.”

Phase 1 Sanitary Sewer System Rehabilitation
Addendum No.1

Questions and Answers

Question 1:

Will the use of water be free of charge to the Contractor?

Answer 1:

Yes

Question 2:

Can hydrants be used on site close to the lines being cleaned?

Answer 2:

Yes. The Town will provide a backflow preventor that must be used.

Question 3:

Are preliners required for all CIPP lining or at the discretion of the lining contractor.

Answer 3:

Preliners are required at the discretion of the lining contractor.

Question 4:

Can you provide flow data from the pump stations that dump into MH 2059 and MH 2057?

Answer 4:

Flow data is available for MH 2057. See below. Flow data is unavailable for MH 2059.

Month	Year	Average Daily Flow (gallons)
September	2018	13,658
October	2018	11,823
November	2018	11,467
December	2018	30,637
January	2019	13,573
February	2019	11,973
March	2019	11,460